



NORTHSHORE UTILITY DISTRICT

Capital Improvement Project

Proposed Sewer Main Rehabilitation Project

ESTIMATED START DATE: Monday, November 2, 2015

ESTIMATED DURATION: Approximately 1 week

CONTRACTOR: PEC, Inc.

WORKING HOURS: Monday thru Friday, 7:30 AM to 5:00 PM

FOR MORE INFO CONTACT: Northshore Utility District

George Matote, Project Manager (NUD)
(425) 398-4400 x121

Pat Pisarsky, Superintendent (Contractor)
(406) 459-5053

Project Description

Northshore Utility District will be trenchlessly rehabilitating the existing sewer mains in Swamp Creek Park utilizing a process called Cured In-Place Pipe (CIPP). The CIPP process will provide a new lining from manhole-to-manhole by inverting a resin impregnated, plastic coated, felt tube into the sewer main by steam pressure. The new lining is then cured in-place by the steam used for the inversion process. The result is a new continuous lining between manholes that is structurally sound.

During the installation of the new liner, you may notice steam exhaust and a strong resin smell as part of the curing process. Please be assured that this is normal and will not harm you or the environment.

Thank you for your patience and cooperation as we trenchlessly rehabilitate the existing sewer mains in the area.

Accountable Management - Responsible Usage